

UNION SIGNATORY

**LABOR
OPERATORS
CEMENT MASON**

DIR# 1000952960
CA LIC# 1009454
DBE # 45754
MBE#20523235

SANTAMARIA CONCRETE

ISN NET CERTIFIED # 400-778710
CGA/DPI # 37560
MC CA#603831
DOT#3504494

CORE COMPETENCIES

- **Concrete:** Flat Concrete Cast-in-place, Sidewalks, Curbs & Gutters, minor concrete, Retaining Walls, Footings, Beams, structural slabs, and ADA Ramps.
- **Asphalt:** Hot Mix Asphalt and Slurry Coat, Milling & Overlays
- **Earthwork:** digs, moves, and places material forming the surface of the earth, cut, fill, excavation, grade, trench, and backfill.
- **Bridge Restoration:** demo unsound concrete, rapid set concrete path, polyester concrete restoration, methacrylate resin restoration, and Joint Seal Type A installation.

Our current California Contractor License Classification includes:

- C-12 - Earthwork and Paving Contractors
- C-8 - Concrete Contractor
- C-31 - Construction Zone Traffic Control Contractor

NAICS CODES:

238110 - Poured Concrete Foundation and Structure Contractors
237310 - Highway, Street, and Bridge Construction
238910 - Site Preparation Contractors



Sonoma
Napa
Solano
Marin
Contra Costa
Alameda
San Francisco
San Mateo
Santa Clara
Santa Cruz
San Benito
Monterey
San Luis Obispo
Santa Barbara
Sacramento
San Joaquin
Stanislaus
Merced
Fresno

Main Office Location: 785 Lincoln Ave, San Jose, CA 95126
(T) 408.634.4209

<http://santamaria-concrete.com>
estimating@santamaria-concrete.com

PAST PERFORMANCE



Polyester Concrete Restoration

Project: 04-4Y990

Client: Caltrans (Emergency Project)

Key Features: Safety is crucial due to the explosive nature of the two components in Polyester Concrete.

Foundation

Project: Davis Service Center New Building Improvements

Prime Contractor: PGE

Key Features: Safe excavation, precise grading, compliant foundations, and beam construction per PGE standards.

Retaining Wall

Project: Operable Unit 2 - Former Napa MGP

Prime Contractor: Severson Environmental Services.

Key Features: Pouring concrete in high temperatures, protecting water evaporation to prevent cracking, and ensuring the proper cure process.

Demo unsound concrete, RSC, and Bridge removal

Project: 04-3W7504

Prime Contractor: American Civil Construction (ACC)

Key Features: Regularly test rebar for oxidation and concrete integrity; ensure rapid-set concrete reaches 3,600 psi before reopening lane.

Placing Hot Mix Asphalt

Project: Operable Unit 1 - Former Vallejo MGP Site

Prime Contractor: Severson Environmental Services

Key Features: Ensure proper grading, base compaction, quality asphalt mix, correct paving temperature, and efficient drainage installation.